

# RECORD COPY

1/4

## PCT REQUEST

2980337PC/su

Original (for SUBMISSION) - printed on 16.08.1999 12:57:47 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/FI 99 / 0 0 6 7 6
0-2	International Filing Date	16 AUG 1999 (16.08.99)
0-3	Name of receiving Office and "PCT International Application"	The Finnish Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.84 (updated 01.07.1999)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	National Board of Patents and Registration (Finland) (RO/FI)
0-7	Applicant's or agent's file reference	2980337PC/su
I	Title of invention	TRACING OF SIGNALLING MESSAGES
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	NOKIA TELECOMMUNICATIONS OY
II-5	Address:	Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	EINAMO, Kari
III-1-5	Address:	Komentajankatu 8 H 61 FIN-02600 Espoo Finland
III-1-6	State of nationality	FI
III-1-7	State of residence	FI

## PCT REQUEST

2980337PC/su


Original (for SUBMISSION) - printed on 16.08.1999 12:57:47 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	KOLSTER OY AB
IV-1-2	Address:	Iso Roobertinkatu 23 P.O. Box 148 FIN-00121 Helsinki Finland
IV-1-3	Telephone No.	+ 358 9 618 821
IV-1-4	Facsimile No.	+ 358 9 602 244
IV-1-5	e-mail	Kolster@Kolster.Fi
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW SD SL SZ UG ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AL AM AT (patent and utility model) AU AZ BA BB BG BR BY CA CH&LI CN CR CU CZ (patent and utility model) DE (patent and utility model) DK (patent and utility model) DM EE (patent and utility model) ES FI (patent and utility model) GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MD MG MK MN MW MX NO NZ PL PT RO RU SD SE SG SI SK (patent and utility model) SL TJ TM TR TT UA UG US UZ VN YU ZA ZW

## PCT REQUEST

2980337PC/su

Original (for SUBMISSION) - printed on 16.08.1999 12:57:47 PM

V-5	<b>Precautionary Designation Statement</b> In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI-1	Priority claim of earlier national application		
VI-1-1	Filing date	18 August 1998 (18.08.1998)	
VI-1-2	Number	981773	
VI-1-3	Country	FI	
VI-2	<b>Priority document request</b> The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1	
VII-1	International Searching Authority Chosen	Swedish Patent Office (ISA/SE)	
VIII	Check list	number of sheets	electronic file(s) attached
VIII-1	Request	4	-
VIII-2	Description	13	-
VIII-3	Claims	3	-
VIII-4	Abstract	1	2980337p.txt
VIII-5	Drawings	2	-
VIII-7	TOTAL	23	
VIII-8	Accompanying items	paper document(s) attached	electronic file(s) attached
VIII-8	Fee calculation sheet	✓	-
VIII-10	Copy of general power of attorney	✓	-
VIII-16	PCT-EASY diskette	-	diskette
VIII-17	Other (specified):	Copy of Official Action	-
VIII-18	Figure of the drawings which should accompany the abstract	3	
VIII-19	Language of filing of the international application	English	
IX-1	Signature of applicant or agent	 Tapio Äkräs	
IX-1-1	Name	KOISTER OY AB	

## FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	16 AUG 1999	(16-08-1999)
------	---	-------------	--------------

## PCT REQUEST

2980337PC/su

Original (for SUBMISSION) - printed on 16.08.1999 12:57:47 PM

10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

## FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--




## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification <sup>7</sup> : <b>H04Q 7/38</b>		<b>A1</b>	(11) International Publication Number: <b>WO 00/11902</b>
			(43) International Publication Date: 2 March 2000 (02.03.00)
(21) International Application Number: PCT/FI99/00676 (22) International Filing Date: 16 August 1999 (16.08.99) (30) Priority Data: 981773 18 August 1998 (18.08.98) FI (71) Applicant (for all designated States except US): NOKIA NETWORKS OY [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI). (72) Inventor; and (75) Inventor/Applicant (for US only): EINAMO, Kari [FI/FI]; Komentajankatu 8 H 61, FIN-02600 Espoo (FI). (74) Agent: KOLSTER OY AB; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).		(81) Designated States: AE, AL, AM, AT, AT (Utility model), AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, CZ (Utility model), DE, DE (Utility model), DK, DK (Utility model), DM, EE, EE (Utility model), ES, FI, FI (Utility model), GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SK (Utility model), SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).  <b>Published</b> <i>With international search report.          Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.</i>	

(54) Title: TRACING OF SIGNALLING MESSAGES

## (57) Abstract

A method, system and network element for tracing signalling messages related to a subscriber in a mobile communication system. In the solution according to the invention a functional entity of the mobile communication system receives a trace command (3-1) which indicates the tracer and identifies at least one subscriber whose signalling messages are to be traced, and tracing is started, tracing comprising the steps of: copying the signalling message in response to reception or transmission of a signalling message related to the subscriber to be traced, and sending a copy to the tracer (3-2').



**FOR THE PURPOSES OF INFORMATION ONLY**

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon			PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

## TRACING OF SIGNALLING MESSAGES

### BACKGROUND OF THE INVENTION

The invention relates to tracing of signalling messages related to a subscriber in a mobile communication system, and particularly to tracing  
5 signalling messages of a specific subscriber.

Mobile communication systems have been developed because it has been necessary to be able to reach people even when they are not close to a fixed telephone terminal. The most important service provided by the mobile communication system is that the subscriber can make a call or he can  
10 be called, regardless of the subscriber's location in the coverage area of the system. Besides the mobile communication systems, the supplementary services provided through mobile stations have also developed. Most of these supplementary services are also available when the mobile subscriber roams from one network to another. To provide the services, the network elements or  
15 processes of the mobile communication system have to exchange information on the subscriber. This information is exchanged using signalling messages. Situations in which the subscriber cannot access the desired service or the service does not function as it should are relatively common. Causes of faults are searched for by tracing signalling messages related to the subscriber. In  
20 the pan-European mobile communication system GSM (Global System for Mobile Communications), for example, tracing is in practice carried out by taking snap shots from the signalling message flow and by analyzing their contents. A snap shot is a temporally limited sample from all signalling between the network elements or processes that are monitored.

25 The problem related to the arrangement described above is that as the signalling load increases, the buffers reserved for snap shots fill up rather quickly, and thus it is probable that the snap shots contain only some of the necessary messages or no necessary messages at all. Even if the signalling load were small, it would not be possible to ensure in any way that the snap  
30 shot contains the signalling messages that are to be traced. A further problem is that snap shots are usually rather large in size, and thus it takes a lot of time and effort to separate necessary messages from the unnecessary messages.

### BRIEF DESCRIPTION OF THE INVENTION

An object of the invention is to provide a method and an apparatus  
35 implementing the method to eliminate the above-mentioned problems. The

objects are achieved with a method according to the invention which comprises transmitting and receiving signalling messages in a functional entity, which is an entity for subscriber mobility management in a mobile communication system, the method being characterized in that said functional entity receives a trace command which indicates the tracer and identifies at least one subscriber whose signalling messages are to be traced, and tracing is started, tracing comprising the following steps:

copying a signalling message in response to reception or transmission of the signalling message related to the subscriber to be traced, and

sending a copy to the tracer.

Here the term 'tracer' refers to the network address or memory address to which copied signalling messages are sent or in which they are stored.

The invention also relates to a system where the method of the invention can be employed. The system of the invention comprises subscribers, at least some of the subscribers being able to roam within the coverage area of the system, one or more network elements which receive and transmit signalling messages to manage subscriber mobility, and operating means for giving instructions to the network element. The system is characterized in that the operating means are arranged to give a trace command to the network element, the command indicating the tracer and identifying at least one subscriber whose signalling messages are to be traced, and the network element is arranged to copy signalling messages related to the subscriber to be traced in response to the trace command and to send a copy to the tracer.

The invention further relates to a network element which can be utilized in the method of the invention. The network element of the invention, which receives and transmits signalling messages to manage subscriber mobility, is characterized in that the network element comprises reception means for receiving the trace command which indicates the tracer and identifies at least one subscriber to be traced whose signalling messages are to be traced, separation means for separating the signalling messages of the subscriber to be traced from other signalling messages, copying means for copying the signalling messages of the subscriber to be traced and transmission means for sending copies to the tracer.



The invention is based on the idea that the network element or process is informed of the subscriber whose messages are to be monitored. After this the network or process automatically carries out monitoring and copies only messages related to this subscriber and sends copies to the desired address where the tracer is. The most important advantage of the invention is that all desired signalling messages can be obtained regardless of the lapse between the messages or whether the messages are sent during a snap shot; not even a single desired message is missed nor is it necessary to search for messages from a large group of irrelevant messages. Furthermore, it is easy to find messages related to one another because they need not be searched from a large group of messages. Usually messages related to one another are successive, and thus it is easy to find them; after all, the messages are sent to the tracer in reception and transmission order. Yet another advantage of the invention is that sending the trace command leads to immediate starting of the tracing. Therefore the fault is discovered as quickly as possible.

In a preferred embodiment of the invention the desired type of the message is also indicated, e.g. messages related to a mobile-terminating call. This has the advantage that the desired messages can be defined more accurately, which makes it even easier to search for the cause of the fault.

In a preferred embodiment of the invention tracing is performed one dialogue at a time. In this case it is advantageous that the messages are obtained as a whole, and thus we do not need to guess what the preceding messages contain.

In a preferred embodiment of the invention copying of messages is not finished until a specific stop command has been received. This has the advantage that the tracer may finish tracing immediately after it has received sufficiently many messages for finding out the fault. If a certain number of messages were always copied, this could lead to copying of too many or too few messages, depending on the case.

Preferred embodiments of the method, system and network element of the invention are disclosed in the appended dependent claims.

#### BRIEF DESCRIPTION OF THE DRAWINGS

The invention will be described in greater detail by means of preferred embodiments with reference to the accompanying drawings, in which

Figure 1 illustrates a mobile communication system,

Figure 2 illustrates an MAP protocol stack,

Figure 3 illustrates signalling according to the invention,

5 Figure 4 is a flow chart of the function according to a first preferred embodiment of the invention, and

Figure 5 is a block diagram of the element according to the first preferred embodiment of the invention.

#### DETAILED DESCRIPTION OF THE INVENTION

10 The present invention is applicable to any mobile communication system which supports mobility, such as the third generation mobile communication systems that are under development, e.g. UMTS (Universal Mobile Telecommunication System) and IMT-2000 (International Mobile Telecommunication 2000). In the following the invention is described in greater detail by examples in connection with the GSM system, but the invention is  
15 not, however, limited to this particular system.

Figure 1 is a simplified block diagram of the GSM system. In the figure all functional elements of the GSM system are located in network elements which have the same names. Functional elements may also be integrated, i.e. placed in the same network element. In that case a functional  
20 element is often called a process. At least a mobile switching centre MSC, visitor location register VLR and home location register HLR are in charge of subscriber services. These are the central functional entities in respect of mobility management, controlling and signalling. They are responsible for roaming, for example. This is a characteristic of the mobile communication  
25 network which enables correct call routing when the mobile subscriber roams from one network or cell to another. For example, roaming guarantees that a call is not interrupted when the mobile user drives from the area of the cell of one base station to the area of another base station. As regards a more detailed description of the GSM system, reference is made to *The GSM*  
30 *System for Mobile Communications*, M. Mouly and M. Pautet, Palaiseau, France 1992, ISBN:2-9507190-07-7.

Referring to Figure 1, the network of the GSM system comprises a base station subsystem BSS and a network subsystem NSS. A mobile station MS is connected to the base station system BSS via a radio path, the base  
35 station system being connected to a mobile switching centre MSC. The mobile

switching centre is responsible for switching calls in which at least one mobile station MS is involved. The mobile switching centre MSC is in contact with other mobile switching centres. Some mobile switching centres MSC are connected to other telecommunications networks ON, such as other public land-based mobile networks PLMN or the public switched telephone network PSTN, and they comprise interconnecting functions for switching calls to and from the networks. The most essential difference between the mobile switching centre MSC and the exchange of a fixed network is that the mobile communication systems only. For example, the mobile switching centre has to consider the influence of radio resource allocation and manage subscriber mobility together with the network registers. Consequently, the mobile switching centre has to carry out certain procedures, such as procedures related to location registration and changeover.

Two types of databases, i.e. registers, are related to call routing. Information on all subscribers in the network is stored permanently or semi-permanently in the home location register HLR, including information on the services the subscriber has access to and the subscriber's current location. The subscriber information comprises e.g. a subscriber identifier, i.e. IMSI (International Mobile Subscriber Identity), and the subscriber's telephone number MSISDN. One IMSI may have several telephone numbers.

The visitor location register VLR is usually connected to one mobile switching centre MSC, but it may also serve several centres. The visitor location register VLR can be integrated into the mobile switching centre MSC. Such an integrated network element is called a visited mobile switching centre MSC/VLR. When the mobile station MS is active (i.e. it has registered with the network and can make or receive a call), most of the subscriber information related to the mobile station MS and included in the home location register HLR is loaded (copied) into the visitor location register VLR of the mobile switching centre MSC in the area of which the mobile station MS is. The information the VLR has on the mobile station includes the IMSI, MSISDN and location area in which the mobile station is registered, and parameters of supplementary services. The VLR needs this information to process calls which terminate to or originate from the mobile station included in its registers.

The quality of services provided by the network is monitored in a network management subsystem NMS, or to be more precise, in an operation

and maintenance centre OMC located in the NMS. From the operation and maintenance centre OMC the network operator can monitor the function of the network elements and change different network parameters. Operation and maintenance units OMU located in the network elements function as interfaces  
5 between the network element and the operator. There is a man machine interface MMI between the operation and maintenance centre and the OMU unit. The operator can give local or remote-controlled commands to the network elements through this interface. The operation and maintenance centre may also comprise smaller operation and maintenance centres, one of  
10 them being the main operation and maintenance centre.

In addition to prior art monitoring means, the mobile communication system implementing the functionality of the present invention also comprises means for tracing signalling messages, i.e. means for receiving a trace command, means for detecting the messages to be traced from a group of  
15 messages, means for copying the message to be traced and means for sending a copy to the tracer. Implementation of these means does not require changes to the equipment because the existing network elements comprise processors and memory which the functions of the invention can employ. All changes needed to implement the invention can be carried out by adding or  
20 updating software routines in the network elements which comprise functions according to the invention.

The mobile communication system uses a mobile application part MAP for transmitting mobile network specific information between the different entities of the same mobile communication network and between the entities  
25 in different mobile communication networks. The MAP protocol is a general name for protocols between the functional elements, and MAP protocols are usually processed as a single protocol. The different network elements or processes must support the MAP protocol to exchange the necessary information so that mobile services can be transmitted. If the functional  
30 elements are integrated into the same network element, they must use the MAP protocol for external communication, and thus they also preferably use the MAP protocol in their internal communication. In their internal data transmission the functional elements can alternatively use another protocol which is, however, used for performing the functions the mobile application  
35 part MAP requires.

An MAP protocol stack according to the GSM system is illustrated in Figure 2. The MAP protocol consists of a number of services the provider of the MAP service, i.e. an MAP entity, offers to the users of MAP services. The users of the MAP service interact with the MAP entity by transmitting or receiving MAP service primitives at the service interface. The MAP service is used by applications which are run above the MAP protocol, such as call control CC, supplementary service SS, mobility management MM and radio resource control RR. In the GSM system all MAP protocols use the services of a TCAP protocol (Transaction Capabilities Application Part) of signalling system SS7, and the TCAP protocol uses services of the SCCP protocol (Signalling Connection Control Part) of SS7. All these protocols use signalling transfer which is provided by the MTP protocol (Message Transfer Part) of the lowest layer. In other mobile communication systems the MAP protocols may use protocols of other signalling systems than SS7.

Figure 3 illustrates signalling according to the first preferred embodiment of the invention. If in the example illustrated in Figure 3 the signalling between A and B occurs in the same network element, it is signalling between processes, i.e. functional elements. If A and B are located in different network elements, signalling occurs between network elements. In both cases network elements receive and transmit messages. A received message means a message received in the signalling between two network elements, and a transmitted message means a message transmitted from a network element. If internal signalling of a network element is involved, in the first preferred embodiment one of the processes is chosen as the process whose received and transmitted messages are monitored. In another embodiment both processes can be monitored. In the example of Figure 3, A denotes a single network element or process, whereas B represents all networks or processes A has a dialogue with. A may be e.g. an MSC which has a dialogue with the VLR and the HLR. B represents these other parties of the dialogue in Figure 3.

Referring to Figure 3, the operation and maintenance centre OMC gives either a local or a remote-controlled trace command to A in signalling message 3-1 (Trace). The signalling message comprises at least the information required for identifying the subscriber, such as the mobile subscriber identifier IMSI or the subscriber's telephone number MSISDN. It is also possible to use other subscriber identifiers, such as a temporary identifier

TMSI. If signalling messages of several subscribers are to be traced, the signalling message 3-1 may include separate identification data of each subscriber or only e.g. the first three digits of the telephone number, in which case signalling messages of each subscriber whose telephone number begins correspondingly are traced. The signalling message 3-1 also indicates the tracer. Depending on the embodiment, the signalling message either always includes the tracer's address or the fact that the address is missing indicates that a default tracer is used or the tracer is the sender of the send command. The tracer may be an element in the operation and maintenance centre OMC, and traced messages are sent to the address of this element. The tracer's address may also be a record in the memory of the network element, from which the information is loaded e.g. into the OMC centre or into a computer at the network element using a separate command. The tracer is by no means connected with the element which gives the trace command, although usually the element that gives the trace command also functions as the tracer. The signalling message 3-1 may also contain information on the desired message type, e.g. signalling related to a call terminating to the subscriber's mobile station.

After A has received message 3-1, it writes down the subscriber, the tracer and the possible message type in its monitoring table. A monitoring table is described in greater detail in connection with Figure 5. Then A starts to monitor the messages it has received and transmitted in a manner to be explained more closely in connection with Figure 4. When it detects a message 3-2 to be traced, it copies it and sends the copy 3-2' to the tracer, which is the OMC in the example of Figure 3. In the first preferred embodiment of the invention A continues monitoring and copying until it receives a command to stop tracing from the OMC in message 3-3 (StopTrace). The stop command contains all the information A needs in order to know which trace is to be stopped. In the first preferred embodiment of the invention message 3-3 includes the same parameters as message 3-1. If message 3-1 identifies more than one subscriber, tracing can be stopped one subscriber at a time. If several tracers have asked to trace messages related to the same subscriber, tracing is preferably stopped one tracer at a time.

Having received message 3-3, A removes the subscriber or subscribers indicated in the message from the monitoring table and stops tracing of their messages.

In another preferred embodiment of the invention the trace command 3-1 is always valid for the duration of one dialogue. When the dialogue ends, A removes the message from the monitoring table and message 3-3 is not needed.

5           The signalling messages described above in connection with Figure 3 are only exemplary and may contain several different messages for transmitting the same information. The messages may also contain other data and they may be combined freely. Furthermore, the names of the messages may change. In addition, other messages, such as acknowledgement  
10           messages of messages 3-1 and 3-3, may be transmitted between these messages.

          Figure 4 illustrates function according to the first preferred embodiment of the invention in a network element which has received a trace command related to a certain subscriber and to messages of a certain type,  
15           e.g. signalling messages related to a mobile-terminating call. In the first preferred embodiment of the invention tracing of signalling messages starts as a dialogue begins. An MAP dialogue is defined as an alternative between two MAP users so that the task can be completed. If the MAP dialogue is related to a specific subscriber, the subscriber's identification data is usually  
20           transmitted in the first MAP message. In some cases, e.g. in signalling of phase 2 related to short messages, the subscriber's identification data is not transmitted until in the second MAP message. In these cases the second message is regarded as the starting message of the dialogue related to the subscriber. Messages of different types can be transmitted during the MAP  
25           dialogue. At its shortest the dialogue comprises the first message and its acknowledgement.

          Referring to Figure 4, a signalling message is received and transmitted in step 400, and in step 401 it is checked whether the message initiates a dialogue, i.e. whether it includes the subscriber's identification data.  
30           The subscriber is identified in the MAP messages using either a subscriber identifier IMSI or a telephone number MSISDN. If the signalling message includes an identifier, it initiates the dialogue. In that case it is checked in step 402 whether the dialogue is to be traced, i.e. whether the subscriber is included in the monitoring table, which is described in greater detail in  
35           connection with Figure 5. If the dialogue is to be traced, it will be added to the list of dialogues to be traced in step 403. Then it is checked in step 404

whether the message is of the desired type. If the message is of the desired type, the signalling message is copied in step 405 and a copy is sent to the tracer in step 406. The tracer's address and possibly the desired message type are obtained from the monitoring table and this information may be  
5 copied into the list of dialogues to be traced. Then we proceed to step 407 where the signalling message is forwarded according to the prior art. Forwarding means that a received message is transferred for processing and a message to be transmitted is transmitted to the other party of the dialogue.

10 If it is detected in step 401 that the message does not include an identifier, it is checked in step 408 whether the message belongs to a dialogue related to the subscriber, i.e. whether it is related to the subscriber. If the message does not belong to a dialogue related to the subscriber, we proceed to step 407 where the message is forwarded. If the dialogue belongs to a dialogue related to the subscriber, we proceed to step 409 where it is checked  
15 whether the dialogue is on the list of the dialogues to be traced. If this is not the case, we proceed to step 407 where the message is forwarded. If the dialogue is on the list of dialogues to be traced, it is checked in step 410 whether the message stops the dialogue, i.e. whether it is the last message. If the message is not the last message, we return to step 404 to check whether  
20 the message is a desired message. If the message is the last message, we proceed to step 411 where the dialogue is removed from the list of dialogues to be traced, after which we return to step 404. In an embodiment where tracing is carried out during one dialogue only, information is also deleted from the monitoring table in step 411.

25 If it is detected in step 402 that the message is not of the desired type, we proceed to step 407 where the signalling message is forwarded. If several trace requests were related to the same subscriber, the check of step 404 and the following actions are carried out one trace request at a time.

30 The steps illustrated in Figure 4 are not in absolute chronological order and some of the steps can be performed simultaneously or deviating from the chronological order described. Other functions may also be performed between the steps. Some of the steps, e.g. the check in step 404, can also be omitted. In some embodiments copying can be started in the middle of a dialogue. In that case the dialogue has to be linked with the  
35 subscriber differently from what was described above. It is essential that received and transmitted signalling messages are monitored and the message



or messages related to the subscriber are picked from among them and a copy of the message is sent to the tracer.

Figure 5 illustrates a network element NE of the invention, such as a mobile switching centre, home location register or visitor location register according to the GSM system. The network element comprises terminals ET for receiving messages from and transmitting messages to other network nodes, an application part AP, which controls the network element, memory M and operation and maintenance unit OMU for receiving commands and instructions from the operator and for answering them. The network element receives the trace command, among other things, via the operation and maintenance unit.

The application part AP comprises different protocol entities, such as an MAP entity ME which transmits MAP services. The MAP entity ME transmits all MAP services of the network element, i.e. all MAP signalling messages are transmitted under the control of the MAP entity. In the first preferred embodiment of the invention the MAP entity carries out the procedures related to tracing in the network element. These procedures were described in greater detail in connection with Figures 3 and 4. In another embodiment these procedures may be carried out by another entity, e.g. an entity of the lower protocol layers or an application entity to be run above the MAP. Procedures may also be divided between different entities. When tracing is carried out at the MAP level, i.e. the MAP entity is responsible for that, the implementation is simpler because at the MAP level information processing is related to the subscriber. A further advantage is that tracing signalling described in Figure 3 may be regarded as part of the MAP protocol.

In the first preferred embodiment the memory of the network element comprises a monitoring table MT, which preferably contains information on the subscribers whose signalling messages are to be traced and information on the tracer, i.e. the address to which copied messages are sent. The monitoring table may also include information on the type of the messages to be traced. If this information is not available, it is assumed that all messages related to the subscriber are to be traced. The information of the monitoring table can be maintained by the OMU or by the MAP entity ME or by both of them. When the network element receives a trace command, the unit maintaining the monitoring table adds the necessary information to the table. If it is told in the trace command that several subscribers should be traced so

that each subscriber is identified separately, the data on each subscriber are added to the monitoring table as if the data were received in separate trace commands. If the trace command identifies a number of subscribers as a single group, e.g. as a group consisting of subscribers having a telephone number beginning with a certain sequence of digits, the data are added as if only one subscriber were involved. Two tracers may be related to the same subscriber, and thus the desired messages may be of the same type or completely different. For example, one of the trace commands related to the same subscriber at the same time may be a command according to which signalling messages related to a mobile-terminating short message are to be sent to the mechanic by to the network element via the operation and maintenance unit OMU. In the other trace command all signalling messages related to the subscriber are copied into the memory of the network element. The information is stored in the monitoring table so that the right tracer receives copies of the correct messages related to the right subscriber or subscribers. In the embodiments where tracing is stopped in response to a stop command, the maintenance unit deletes the subscribers indicated in the stop command as well as information on them from the monitoring table. In the embodiments where tracing is performed one dialogue at a time the information related to the subscriber to be traced is deleted from the monitoring table after the dialogue has ended.

In the first preferred embodiment of the invention a dialogue list (not shown) mentioned in connection with Figure 4 is also stored in the memory M, i.e. a list on the dialogues to be traced which is used for monitoring on-going dialogues. This list is preferably maintained by the MAP entity ME. If the command to stop tracing is received in the middle of an on-going dialogue, the dialogue is not monitored till its end in the first preferred embodiment of the invention, but the dialogue related to the subscriber is deleted from the dialogue list because of the stop trace command. In another embodiment copying and sending of copied messages are not stopped until the dialogue that was possibly going on when the stop command was received ends.

The saving format of information described above is only an example. In other embodiments it is possible to use different data structures and ways of storing information. It is essential that information is available on the subscriber to be traced and the tracer.

It is to be understood that the above description and the figures related to it are only intended to illustrate the present invention. It will be obvious to a person skilled in the art that the invention may be modified in different ways without deviating from the scope and spirit of the invention disclosed in the appended claims.

## CLAIMS

1. A method of tracing signalling messages of a subscriber in a mobile communication system which comprises functional entities for subscriber mobility management, the method comprising

5 transmitting and receiving signalling messages in a functional entity, **characterized by**

receiving a trace command (3-1) in said functional entity, the command indicating the tracer and identifying at least one subscriber whose signalling messages are to be traced,

10 starting tracing which comprises the steps of:

copying a signalling message in response to the reception or transmission (405) of a signalling message related to the subscriber to be traced, and

sending a copy to the tracer (460, 3-2').

15 2. A method according to claim 1, **characterized** in that the trace command also indicates the type of the signalling message to be traced, and

the signalling message is copied only if it is of the type (404) to be traced.

20 3. A method according to claim 1 or 2, **characterized** in that tracing starts from the start message (401) of a dialogue related to the subscriber to be traced.

4. A method according to claim 3, **characterized** in that tracing of the subscriber's signalling message stops in response to the fact  
25 that the dialogue which started tracing ends.

5. A method according to claim 1, 2 or 3, **characterized by** receiving a stop command (3-3) of tracing in the entity, the command indicating the subscriber whose signalling message tracing is to be stopped, and

30 stopping tracing of the signalling messages related to said subscriber.

6. A method according to any one of the preceding claims, **characterized** in that the signalling messages of the MAP protocol are traced.

35 7. A mobile communication system comprising

subscribers (MS), at least some of the subscribers being able to roam within the coverage area of the system,

one or more network elements (MSC, VLR, HLR) in which signalling messages are received and transmitted to manage subscriber mobility,

5       operating means (OMC) for giving instructions to the network element,

**characterized** in that

the operating means (OMC) are arranged to give a trace command to the network element (MSC, VLR, HLR), the command indicating the tracer  
10       and identifying at least one subscriber (MS) whose signalling messages are to be traced,

the network element (MSC, VLR, HLR) is arranged to copy signalling messages related to the subscriber (MS) in response to the trace command and to send a copy to the tracer.

15       8. A system according to claim 7, **characterized** in that the trace command also indicates the type of the signalling message to be traced, and

the network element (MSC, VLR, HLR) is arranged to copy the signalling message related to the subscriber to be traced if it is of the type to  
20       be traced.

9. A system according to claim 7 or 8, **characterized** in that the signalling messages to be traced are messages of the MAP protocol, and

the network element (MSC, VLR, HLR) is arranged to start copying  
25       of the signalling messages related to the subscriber in response to the dialogue of the MAP protocol which starts after the trace command and is related to the subscriber to be traced.

10. A network element (NE) of a mobile communication system which receives and transmits signalling messages to manage subscriber mobility, **characterized** in that the network element comprises  
30       

reception means (OMU) for receiving a trace command, which indicates the tracer and identifies at least one subscriber whose signalling messages are to be traced,

separation means (ME) for separating the signalling messages of  
35       the subscriber to be traced from other signalling messages,

copying means (ME) for copying the signalling messages related to the subscriber to be traced, and

transmission means (ME, OMU) for sending copies to the tracer.

11. A network element according to claim 10, **characterized**  
5 in that

the trace command also indicates the type of the dialogue to be traced, and

the separation means (ME) are arranged to separate the signalling messages that belong to the dialogue of the type to be traced from the  
10 signalling messages of the subscriber to be traced.

12. A network element according to claim 10 or 11, **characterized** in that the network element (NE) comprises an MAP entity (ME) which is responsive to the reception means and comprises separation, copying and transmission means.

1/2








FIG. 2

FIG. 3



2/2





# INTERNATIONAL SEARCH REPORT

International application No.

PCT/FI 99/00676

## A. CLASSIFICATION OF SUBJECT MATTER

IPC7: H04Q 7/38

According to International Patent Classification (IPC) or to both national classification and IPC

## B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC7: H04Q

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

SE,DK,FI,NO classes as above

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

## C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	WO 9615643 A1 (TELEFONAKTIEBOLAGET LM ERICSSON), 23 May 1996 (23.05.96), page 46, line 19 - page 51, line 25 --	1-12
A	WO 9529554 A1 (DETEMOBIL DEUTSCHE TELEKOM MOBILFUNK GMBH), 2 November 1995 (02.11.95), abstract --	1-12
A	US 5592530 A (PIERCE E. BROCKMAN ET AL), 7 January 1997 (07.01.97), abstract -- -----	1-12



Further documents are listed in the continuation of Box C.



See patent family annex.

\* Special categories of cited documents:

- "A" document defining the general state of the art which is not considered to be of particular relevance
- "E" earlier document but published on or after the international filing date
- "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- "O" document referring to an oral disclosure, use, exhibition or other means
- "P" document published prior to the international filing date but later than the priority date claimed

"I" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance: the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance: the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search

13 January 2000

Date of mailing of the international search report

19 -01- 2000

Name and mailing address of the ISA/  
Swedish Patent Office  
Box 5055, S-102 42 STOCKHOLM  
Facsimile No. +46 8 666 02 86

Authorized officer

Stefan Hansson/cs  
Telephone No. +46 8 782 25 00

# INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.

PCT/FI 99/00676

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 9615643 A1	23/05/96	AU 3942395 A BR 9509723 A CA 2204992 A SE 9701723 A US 5734977 A US 5978669 A	06/06/96 21/10/97 23/05/96 08/07/97 31/03/98 02/11/99
WO 9529554 A1	02/11/95	AT 156641 T AU 2066095 A DE 4414500 A DE 19580370 D DE 59500481 D DK 757871 T EP 0757871 A,B SE 0757871 T3 ES 2108578 T GR 3025300 T ZA 9503344 A	15/08/97 16/11/95 02/11/95 00/00/00 00/00/00 02/03/98 12/02/97 16/12/97 27/02/98 09/01/96
US 5592530 A	07/01/97	NONE	

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

15

Applicant's or agent's file reference 2980337PC/nu	<b>FOR FURTHER ACTION</b> See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/FI99/00676	International filing date (day/month/year) 16.08.1999	Priority date (day/month/year) 18.08.1998
International Patent Classification (IPC) or national classification and IPC <sub>7</sub> H 04 Q 7/38		
Applicant Nokia Networks OY et al		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 4 sheets, including this cover sheet.

☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of \_\_\_\_\_ sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand  15.03.2000	Date of completion of this report  21.11.2000
Name and mailing address of the IPEA/SE Patent- och registreringsverket Box 5055 S-102 42 STOCKHOLM Facsimile No. 08-667 72 88	Authorized officer  Stefan Hansson/mj Telephone No. 08-782 25 00

## INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00676

**I. Basis of the report****1. With regard to the elements of the international application:\***

- ☒ the international application as originally filed
- ☐ the description:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the claims:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, as amended (together with any statement) under article 19  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the drawings:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_
- ☐ the sequence listing part of the description:  
pages \_\_\_\_\_, as originally filed  
pages \_\_\_\_\_, filed with the demand  
pages \_\_\_\_\_, filed with the letter of \_\_\_\_\_

**2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.**These elements were available or furnished to this Authority in the following language English which is:

- ☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).
- ☒ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

**3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:**

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer-readable form is identical to the written sequence listing has been furnished.

**4. ☐ The amendments have resulted in the cancellation of:**

- ☐ the description, pages \_\_\_\_\_
- ☐ the claims, Nos. \_\_\_\_\_
- ☐ the drawings, sheet/fig \_\_\_\_\_

**5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2 (c)).\*\***

\* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

\*\* Any replacement sheet containing such amendments must be referred to under item I and annexed to this report.

## INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00676

**V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement****1. Statement**

Novelty (N)	Claims	<u>1-12</u>	YES
	Claims		NO
Inventive step (IS)	Claims	<u>1-12</u>	YES
	Claims		NO
Industrial applicability (IA)	Claims	<u>1-12</u>	YES
	Claims		NO

**2. Citations and explanations (Rule 70.7)**The claimed invention

The claimed invention relates to a method, system and network element for tracing signalling messages related to a subscriber in a mobile communication system. A functional entity of the mobile communication system receives a trace command that indicates the tracer and identifies at least one subscriber whose signalling messages are to be traced. Tracing is started, the tracing comprising the steps of copying the signalling message in response to reception or transmission of a signalling message related to the subscriber to be traced and sending a copy to the tracer.

The following documents have been cited in the International Search Report

D1: WO 9615643 A1

D2: WO 9529554 A1

D3: US 5592530 A

D1 relates to a method for detecting fraud in a cellular telephone system. Fraud is suspected when the system detects a multiple access from a mobile station, when an activity collision occurs, when the system receives a premature registration from the mobile station, when auditing or operator-initiated locating of the mobile station reveals the existence of the mobile station in two locations simultaneously, or when tracing of mobile subscriber activity reveals unusual activity. On page 46, line 19- 35, D1 describes how some of the mobile station activities are reported to the home system. Whenever tracing is activated, the serving exchange will continuously report to the home system all mobile activities that have been selected for tracing.

.../...

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/FI99/00676

**Supplemental Box**

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: V.

The activity reporting (tracing) is terminated when the tracing is deactivated. However, tracing of activities is not the same as tracing of signalling messages. By capturing signalling messages, all information relating to establishment of a certain activity is received whereas by compiling statistics on activities the only information received is that an activity took place or failed.

Documents D2 and D3 are considered to merely disclose the state of the art and are not commented on further.

Consequently, the claimed invention as in claims 1-12 is considered to be novel, to involve an inventive step and to have industrial applicability.